



D : 900 mm for terminal posts  
750 mm for line posts

NOTES:

1. Remove all sod and organic material and apply weed killer liberally prior to installation of gravel in excavation. Backfill any low areas with 75 mm minus gravel.
2. Concrete to be 20 MPa at 28 days, 75 mm max. slump, 25 mm max. aggregate, and 4 - 6% entrained air.
3. Expansion joints to be at 7.5 m intervals using approved 13mm thick precast expansion joint material. Dummy joints to be at 1.5m intervals.
4. Sidewalk to be installed to alignment and grades shown on the design drawing. Minimum longitudinal grade to be 0.30%. Sidefall to be 2% unless otherwise specified.



**MUNICIPALITY OF CENTRAL SAANICH**

TITLE:

**CONCRETE SIDEWALK**

STD.DWG.No.

**509**

Approved;

Date; SEPT. 1986

Scale; N.T.S.

Rev.